


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Stafford</u>		<u>SE</u> 1/4 <u>NW</u> 1/4 NW 1/4	<u>14</u>	T <u>24</u> S	R <u>15</u> EW
Distance and direction from nearest town or city street address of well if located within city? <u>1/2 north east of Macksville</u>					
2 WATER WELL OWNER: <u>Vernon Doran</u>					
RR#, St. Address, Box # : <u>R.R.</u>			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : <u>Macksville, Ks. 67557</u>			Application Number: <u>35,100</u>		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>75</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. <u>14</u> ft. 2. <u>14</u> ft. 3. <u>14</u> ft.			
		WELL'S STATIC WATER LEVEL <u>14</u> ft. below land surface measured on mo/day/yr <u>4-28-81</u>			
		Pump test data: Well water was <u>60</u> ft. after <u>1</u> hours pumping <u>850</u> gpm			
		Est. Yield <u>900</u> gpm: Well water was <u>62</u> ft. after <u>1 1/2</u> hours pumping <u>900</u> gpm			
		Bore Hole Diameter <u>29</u> in. to <u>75</u> ft., and <u>75</u> in. to <u>75</u> ft.			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued <u> </u> Clamped <u> </u>			
☐ Steel 3 RMP (SR)		Welded <u> X </u>			
☐ PVC 4 ABS		Threaded <u> </u>			
Blank casing diameter <u>16</u> in. to <u>55</u> ft., Dia <u> </u> in. to <u> </u> ft., Dia <u> </u> in. to <u> </u> ft.		Casing height above land surface <u>18</u> in., weight <u> </u> lbs./ft. Wall thickness or gauge No. <u>7</u>			
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
☐ Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) <u> </u>		12 None used (open hole)			
☐ Brass 4 Galvanized steel 6 Concrete tile 9 ABS					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
☐ Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
☒ Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) <u> </u>					
SCREEN-PERFORATED INTERVALS: From <u>55</u> ft. to <u>75</u> ft., From <u> </u> ft. to <u> </u> ft.					
GRAVEL PACK INTERVALS: From <u>10</u> ft. to <u>85</u> ft., From <u> </u> ft. to <u> </u> ft.					
6 GROUT MATERIAL: ☒ Neat cement 2 Cement grout 3 Bentonite 4 Other <u> </u>					
Grout Intervals: From <u>0</u> ft. to <u>10</u> ft., From <u> </u> ft. to <u> </u> ft., From <u> </u> ft. to <u> </u> ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
☒ Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
☐ Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) <u> </u>					
☐ Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? <u>NE</u>		How many feet? <u>1/4 mile</u>			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	4	Top soil			
4	8	Brown clay			
8	18	Brown and white clay			
18	48	Sandy clay-fine sand			
48	75	Sand and gravel			
75	85	Fire clay			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>7-1-81</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>134</u> This Water Well Record was completed on (mo/day/yr) <u>7-22-81</u> under the business name of <u>Rosencrantz-Bemis Ent.</u> by (signature) <u>Ara Dodson</u>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					