

LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 093 STAFFORD SE 1/4 SW 1/4 NE 1/4 23 T24 S R 15 W

Distance and direction from nearest town or city street address of well if located within city?
 1 1/2 E. OF MACKSVILLE, KANS.

2 WATER WELL OWNER: SUITER, DON 023
 RR#, St. Address, Box #: Board of Agriculture, Division of Water Resources

City, State, ZIP code : MACKSVILLE, KS 67557- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

WELL'S STATIC WATER LEVEL 35 ft. below land surface measured on mo/day/yr 7 /17/90
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 80 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 60 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 80 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 80 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 4 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: CATTLE PASTURE
 Direction from well? ALL How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	5	SILT & SAND			
5	8	GREY CLAY			
8	14	BROWN CLAY			
14	40	TAN CLAY			
40	47	GYPSUM			
47	52	TAN CLAY			
52	66	05 SAND AND 17 GRAVEL			
66	68	TAN CLAY			
68	80	17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 7 /17/ 91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 07/07/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse