

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <u>Edwards</u>	Fraction <u>1/4 1/4 1/4</u>	Section number <u>25</u>	Township number <u>T 24 S</u>	Range number <u>R 17 E/W</u>
2. Distance and direction from nearest town or city: <del>6.6 miles</del> <u>1/2 S 2 1/2 W of Belpre</u> Street address of well location if in city:			3. Owner of well: <u>Jerry Stapleton</u> R.R. or street: City, state, zip code: <u>Belpre, Ks.</u>		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. <u>29</u> in. Completion date <u>S-28-76</u> Well depth <u>90</u> ft.	
5. Type and color of material		From		To	
		<u>Sandy Top Soil</u>		<u>0</u>	<u>2</u>
		<u>Brown Clay</u>		<u>2</u>	<u>5</u>
		<u>Gray Clay</u>		<u>5</u>	<u>11</u>
		<u>White &amp; Gray Clay</u>		<u>11</u>	<u>16</u>
		<u>Redish Clay &amp; Fine Sand</u>		<u>16</u>	<u>38</u>
		<u>Sand &amp; Gravel Clean</u>		<u>38</u>	<u>62</u>
		<u>Sand &amp; Gravel Clay Streaks</u>		<u>62</u>	<u>87</u>
		<u>Brown Clay</u>		<u>87</u>	<u>126</u>
		<u>Blue Clay</u>		<u>126</u>	<u>130</u>
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
				9. Casing: Material <u>Steel</u> Height: <u>Above or below</u> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>90</u> ft. depth; Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth; gage No. <u>?</u>	
				10. Screen: Manufacturer's name <u>Doerrs</u> Type <u>Steel</u> Dia. <u>16</u> Slots/grooves <u>3/16</u> Length <u>32</u> Set between <u>58</u> ft. and <u>90</u> ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input type="checkbox"/> Size range of material <u>1/2 3/4 3/8</u>	
				11. Static water level: <input type="checkbox"/> mo./day/yr. <u>26</u> ft. below land surface Date <u>12-2-76</u>	
				12. Pumping level below land surfaces: <u>25</u> ft. after <u>1/2</u> hrs. pumping <u>1200</u> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <u>1400+</u> g.p.m.	
				13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <u>12-3-75</u>	
				14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade	
				15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
				16. Nearest source of possible contamination: <u>1.5</u> mi. Direction <u>West</u> Type <u>Corral</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>WLR</u> Model number <u>5 CHC-12</u> HP <u>60</u> Volts <input type="checkbox"/> Length of drop pipe <u>70</u> ft. capacity <u>1200</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
		(Use a second sheet if needed)			
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz-Bemis 134</u> Business name License No. Address <u>Great Bend, Ks.</u> Signed <u>Judith Rodam</u> Date <u>9/29/76</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

T 24 S 17 E  
 R 17 E  
 Sec 25  
 1/4 1/4 1/4  
 CNE  
 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5