

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 024 EDWARDS NE 1/4 NE 1/4 NE 1/4 21 T 24 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?  
 2 W. 2.N OF LEWIS,KS.

2 WATER WELL OWNER: THERON MCKINNEY 434 Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: R.R.  
 City, State, ZIP code : LEWIS, KS 67552- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 76 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 42 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 42 ft. below land surface measured on mo/day/yr  
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 8.75 in. to 76 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 56 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 15 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 56 ft. to 76 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 76 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 4 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 01 SEPTIC TANK  
 Direction from well? NW How many feet? 70

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	SILT & SAND			
4	6	GREY CLAY			
6	42	TAN CLAY			
42	48	17 GRAVEL			
48	55	CLAY AND 05 SAND			
55	73	05 SAND AND 17 GRAVEL			
73	76	TAN CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 2 /17/99 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 03/04/99 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse