


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well:	County: <b>EDWARDS</b>	Township name: <b>Kinsley NE NE</b>	Fraction: <b>NE NE</b>	Section number: <b>9</b>	Town number: <b>24</b>	Range number: <b>19</b>		
Distance and direction from nearest town or city: <b>3 1/2 N. OF Kinsley</b>				3 Owner of well: <b>Robert BURCHER JR.</b>				
Street address of well location if in city:				Address: <b>Kinsley, Kansas</b>				
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:			4 Well depth: <b>76</b> ft. Date of completion <b>7-16-75</b> Well diameter <b>3 1/2</b> in.		
2 Type and color of material			From		To			
			<b>Top Soil</b>		<b>0 3</b>		5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
			<b>Sandy Clay</b>		<b>3 14</b>		6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input checked="" type="checkbox"/> <b>PASTURE</b>	
			<b>SOFT Yellow Clay (Trace of Water)</b>		<b>4 26</b>		7 Casing: Material <b>RMP</b> Height: above/below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <b>24</b> in. Diam. <b>5</b> in. to <b>76</b> ft. depth! Weight <b>200</b> lbs./ft. Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
			<b>LT. Brown Clay</b>		<b>26 46</b>		8 Screen: <b>Gless &amp; Lowell</b> Manufacturer <b>RMP</b> Dia. <b>3 1/2</b> Slot/gauze <b>5/16</b> Length <b>18'</b> Set between <b>52</b> ft. and <b>26</b> ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material	
			<b>Sand Stone</b>		<b>46 47</b>		9 Static water level: <b>27</b> ft. below land surface Date <b>7-16-75</b>	
			<b>Clay with Gyp</b>		<b>47 56</b>		10 Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.	
			<b>Sand Stone</b>		<b>56 57</b>		11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ____	
			<b>Sand &amp; Clay</b>		<b>57 68</b>		12 Well head completion: <input type="checkbox"/> Pitless adapter <b>24"</b> inches above grade	
			<b>Gravel, Clay, Brown chipped Rock (Water)</b>		<b>68 74</b>		13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From <b>4</b> ft. to <b>14</b> ft.	
<b>Heavy Red Clay (Touch)</b>		<b>74 76</b>		14 Nearest source of possible contamination: ft. <b>30</b> Direction <b>West</b> Type <b>Feed Lot</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No				
2164' (use a second sheet if needed)					15 Pump: <input type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
16 Remarks: elevation <b>Drilled this well and own well finish to standards for cent pump. Carl Hayse</b> <b>Robert Burcher Jr.</b>					17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Carl Hayse</b> <b>SECD 224</b> Business name _____ License No. _____ Address <b>Greensburg Kans</b> Signed <b>Carl Hayse</b> Date <b>7-16-75</b> Authorized representative			

24 19 W 9 N E NE 1/4