

WATER WELL RECORD Form WWC-5 KSA 82a-1212

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Harvey</u>		<u>NE 1/4 NE 1/4 NW 1/4</u>	<u>2</u>	<u>T 24 S</u>	<u>R 2 E</u>
Distance and direction from nearest town or city street address of well if located within city?					
<u>520 W. 6th, Halstead, KS</u>					
2 WATER WELL OWNER: <u>USD #440/Halstead High School</u>					
RR#, St. Address, Box # : <u>520 W. 6th</u>			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : <u>Halstead, KS</u>			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>25'</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. <u>14'</u> ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>16'8"</u> ft. below land surface measured on mo/day/yr <u>9-30-97</u>			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm; Well water was ft. after hours pumping gpm			
		Bore Hole Diameter: <u>8 1/2"</u> in. to <u>25'</u> ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only <u>0</u> Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No <u>(No)</u>			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped <u>2 PVC</u> 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Threaded <u>X</u>					
Blank casing diameter <u>2.375</u> in. to <u>10'</u> ft., Dia in. to ft., Dia in. to SDR <u>13</u> ft.					
Casing height above land surface <u>Flush Mt.</u> in., weight lbs./ft. Wall thickness or gauge No. <u>SCH 40</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot <u>3 Mill slot</u> 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From <u>25'</u> ft. to <u>10'</u> ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From <u>25'</u> ft. to <u>8'</u> ft., From ft. to ft.					
6 GROUT MATERIAL:					
Grout Intervals: From <u>8'</u> ft. to <u>4'</u> ft., From <u>4'</u> ft. to <u>0'</u> ft., From ft. to ft. What is the nearest source of possible contamination: <u>3</u> 1 Septic tank 4 Lateral lines 7 Pit privy <u>1</u> Fuel storage <u>Fuel</u> 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 16 Other (specify below)					
Direction from well <u>Southwest</u> How many feet? <u>95'</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	.50	Asphalt			
.50	4	Dk brn-blk clay, w/ fine-med sand, moist, no odor.			
4	10	Lt brn silty clay to clay w/ caliche, moist, no odor.			
10	19	Med-dk brn clay to silty clay, some caliche stringers, firm, no odor, moist.			
19	23	Gray fine clayey sand, wet, no odor, oxide stringers.			
23	25	Tan fine grained sand, no odor, wet, well rounded.			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>9-30-97</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>539</u> This Water Well Record was completed on (mo/day/yr) <u>10-7-97</u>					
under the business name of <u>J. Environmental Drilling</u> by (signature) <u>James Burke</u>					