


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Harvey		SE 1/4 SE 1/4 NE 1/4	2	T 24 S	R 2 W
Distance and direction from nearest town or city street address of well if located within city? In City Limits-1004 W. 11th Terrace, Halstead					
2 WATER WELL OWNER: Marion Stutzman					
RR#, St. Address, Box # : 1004 W. 11th Terrace				Board of Agriculture, Division of Water Resources	
City, State, ZIP Code : Halstead, KS 67056				Application Number:	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 60 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 27 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 27 ft. below land surface measured on mo/day/yr 10-5-92			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 1.5-2.0 gpm: Well water was 30 ft. after 1 hours pumping .8 gpm			
		Bore Hole Diameter 8 in. to 60 ft., and in. to ft.			
WELL WATER TO BE USED AS:					
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)					
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well					
Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes X No					
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped					
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded					
7 Fiberglass Threaded					
Blank casing diameter 5 in. to 50 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 12 in., weight 2.37 lbs./ft. Wall thickness or gauge No. 21.4					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement					
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)					
3 Mill slot 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)					
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes					
7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 50 ft. to 60 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 25 ft. to 60 ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 5 ft. to 25 ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
13 Insecticide storage					
Direction from well? West How many feet? 100ft					
FROM		TO		LITHOLOGIC LOG	
FROM		TO		PLUGGING INTERVALS	
0		2		Top Soil	
2		7		Gray Clay	
7		25		Tan Clay	
25		29		Gray Clay	
29		48		Fine Sand	
48		60		Fine Sand with Clay layers	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-5-92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/yr) 10-7-92 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					