


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County HARVEY	Township name LAKIN	Fraction NE 1/4 SE 1/4	Section number 4	Town number T-24-5	Range number R-2-W																																																				
Distance and direction from nearest town or city: 1 1/2 mile SW of			3 Owner of well: STAN Robuck																																																							
Street address of well location if in city: HALSTEAD			Address: RR #2 HALSTEAD																																																							
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:																																																							
<table border="1"><thead><tr><th>2</th><th>Type and color of material</th><th>From</th><th>To</th></tr></thead><tbody><tr><td></td><td>loam - sandy</td><td>0</td><td>5</td></tr><tr><td></td><td>SAND (dune type)</td><td>5</td><td>16</td></tr><tr><td></td><td>SAND med size</td><td>16</td><td>18</td></tr><tr><td></td><td>gravel</td><td>18</td><td>26</td></tr><tr><td></td><td>SAND - CLAY MIX</td><td>26</td><td>29</td></tr><tr><td></td><td>DARK CLAY</td><td>29</td><td>32</td></tr><tr><td></td><td>RED - brown clay</td><td>32</td><td>40</td></tr><tr><td></td><td>red-brown to grey clay</td><td>40</td><td>45</td></tr><tr><td></td><td>dark clay - sandy</td><td>45</td><td>48</td></tr><tr><td></td><td>SAND</td><td>48</td><td>50</td></tr><tr><td></td><td>SAND + clay mix</td><td>50</td><td>55</td></tr><tr><td></td><td>SAND - med to coarse</td><td>55</td><td>80</td></tr></tbody></table>			2	Type and color of material	From	To		loam - sandy	0	5		SAND (dune type)	5	16		SAND med size	16	18		gravel	18	26		SAND - CLAY MIX	26	29		DARK CLAY	29	32		RED - brown clay	32	40		red-brown to grey clay	40	45		dark clay - sandy	45	48		SAND	48	50		SAND + clay mix	50	55		SAND - med to coarse	55	80	4 Well depth: 80' ft. Date of completion 8/28/75 Well diameter 4 in.			
			2	Type and color of material	From	To																																																				
				loam - sandy	0	5																																																				
				SAND (dune type)	5	16																																																				
				SAND med size	16	18																																																				
				gravel	18	26																																																				
				SAND - CLAY MIX	26	29																																																				
				DARK CLAY	29	32																																																				
				RED - brown clay	32	40																																																				
				red-brown to grey clay	40	45																																																				
	dark clay - sandy	45	48																																																							
	SAND	48	50																																																							
	SAND + clay mix	50	55																																																							
	SAND - med to coarse	55	80																																																							
5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																																																										
6 Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well																																																										
7 Casing: Material PVC Height: above 11 1/2' Threaded ☐ Welded ☒ Surface 18 in. Diam. 5" Weight 2.20 lbs./ft. + 18 in. to 80 ft. depth Drive shoe? ☐ Yes ☒ No in. to in. ft. depth																																																										
8 Screen: CERT Teed Manufacturer OWN slot Type PVC Dia. 5" Slot/gauze 0046B Length 20' Set between 60 ft. and 80 ft. Fittings: 1/8 - 1/4" Gravel pack ☒ Yes ☐ No Size range of material																																																										
9 Static water level: 18 1/2 ft. below land surface Date 8/28/75																																																										
10 Pumping level below land surfaces: 30 ft. after 1 1/2 hrs. pumping 20 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 80 g.p.m.																																																										
11 Water sample submitted: ☐ Yes ☒ No Date																																																										
12 Well head completion: ☒ Pitless adapter ☐ Inches above grade																																																										
13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 10 ft. to 0 ft.																																																										
14 Nearest source of possible contamination: house sewer line ft. 45 Direction South Type Well disinfected upon completion? ☒ Yes ☐ No																																																										
15 Pump: ☐ Not installed Manufacturer's name AERMOTOR Model number SD-12-75 HP 3/4 Volts 230 Length of drop pipe 70 ft. capacity 18 g.m.p. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																																										
16 Remarks: elevation Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PAUL'S INC 175 Business name License No. Address HESSON BOX 26 Signed Paul Paul Date 8/28/75 Authorized representative																																																							