

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number																																											
County: HARVEY		NE 1/4 NE 1/4 NW 1/4		24		T 24 S		R 2 EW																																											
Distance and direction from nearest town or city street address of well if located within city? 3 mile So Halstead																																																			
2 WATER WELL OWNER: Larry Faudel RR#, St. Address, Box #: RR #2 City, State, ZIP Code: Halstead, KS 67056 Board of Agriculture, Division of Water Resources Application Number:																																																			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			4 DEPTH OF COMPLETED WELL: 46' ft. ELEVATION:																																																
			Depth(s) Groundwater Encountered 1. 27 ft. 2. ft. 3. ft.																																																
			WELL'S STATIC WATER LEVEL 13 ft. below land surface measured on mo/day/yr 8-3-87																																																
			Pump test data: Well water was 27 ft. after 2 hours pumping 30 gpm																																																
			Est. Yield 45 gpm: Well water was ft. after hours pumping gpm																																																
			Bore Hole Diameter 12 in. to 46 ft. and in. to ft.																																																
WELL WATER TO BE USED AS:			5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well																																																
Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted																																																			
Water Well Disinfected? Yes X No																																																			
5 TYPE OF BLANK CASING USED:																																																			
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 6 in. to 35 ft. Dia in. to ft. Dia in. to ft. Casing height above land surface 18 in. weight 3.36 lbs./ft. Wall thickness or gauge No. .225																																																			
TYPE OF SCREEN OR PERFORATION MATERIAL:																																																			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped Factory 8 Saw cut .030 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)																																																			
SCREEN-PERFORATED INTERVALS: From 35 ft. to 45 ft. From ft. to ft.																																																			
GRAVEL PACK INTERVALS: From 15 ft. to 0 ft. From ft. to ft.																																																			
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other																																																			
Grout intervals: From 15 ft. to 0 ft. From ft. to ft. From ft. to ft.																																																			
What is the nearest source of possible contamination:																																																			
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage																																																			
Direction from well? East How many feet? 200'																																																			
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>5</td> <td>Sandy loam</td> <td></td> <td></td> <td></td> </tr> <tr> <td>5</td> <td>10</td> <td>red brown clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>10</td> <td>19</td> <td>Sandy clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>19</td> <td>23</td> <td>Light tan / grey clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>23</td> <td>27</td> <td>Light grey clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>27</td> <td>46</td> <td>Sand - med to very coarse</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	0	5	Sandy loam				5	10	red brown clay				10	19	Sandy clay				19	23	Light tan / grey clay				23	27	Light grey clay				27	46	Sand - med to very coarse			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG																																														
0	5	Sandy loam																																																	
5	10	red brown clay																																																	
10	19	Sandy clay																																																	
19	23	Light tan / grey clay																																																	
23	27	Light grey clay																																																	
27	46	Sand - med to very coarse																																																	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-10-87 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 457 This Water Well Record was completed on (mo/day/yr) 8-31-87 under the business name of United Water Well & Pump by (signature) Paul Burch																																																			
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.																																																			

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4