


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Harvey	Fraction center of NW 1/4	Section number 30	Township number T 24 S	Range number R 2 E
2. Distance and direction from nearest town or city: Street address of well location if in city: 3 E. of Patterson			3. Owner of well: Don Linnebur R.R. or street: Colwich, Kansas 67030 City, state, zip code:			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 3/19/77 Well depth 84 ft.		
		open field		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Topsoil		0	1	9. Casing: Material C-Asb Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 58 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 314		
Fine Sand		1	15	10. Screen: Manufacturer's name Johnson Type Cement-Asb Dia. 16" Slot/Grauze 1/4" Length 26' Set between 58 ft. and 84 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 3/8		
Gravel - Med		15	20	11. Static water level: ☐ mo./day/yr. 16 ft. below land surface Date 3/18/77		
Clay-gray		20	30	12. Pumping level below land surfaces: 24 ft. after 2 hrs. pumping 700 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 800 g.p.m.		
Large Sand		30	45	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
Clay		45	55	14. Well head completion: ☐ Pitless adapter 12 inches above grade		
Good Gravel		55	85	15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: ft. None Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name Peerless Model number 7103 HP 40 Volts ☐ Length of drop pipe 60 ft. capacity 750 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name Weninger License No. 1/4 Address Maize, Ks. Signed Weninger Date 3/22/77 Authorized representative		
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						