

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County: <u>HARVEY</u>	Fraction: <u>CENTER 1/4 SW 1/4</u>	Section number: <u>33</u>	Township number: <u>T 24 S</u>	Range number: <u>R 2</u>	NW
2. Distance and direction from nearest town or city: <u>2 WEST</u>			3. Owner of well: <u>Kenneth Krauss</u>			
Street address of well location if in city: <u>630. HALSTEAD</u>			R.R. or street: <u>RR 11</u>			
			City, state, zip code: <u>SEDAWICK KANS 67135</u>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>32</u> in. Completion date <u>5-4-77</u>		
				Well depth <u>140</u> ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material <u>PVC</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>18</u> in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia <u>1 1/2</u> in. to <u>1 1/2</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>0429</u>		
5. Type and color of material			From	To	10. Screen: Manufacturer's name	
<u>Top soil</u>			<u>0</u>	<u>2</u>	<u>JET STREAM</u>	
<u>CLAY, SANDY</u>			<u>2</u>	<u>15</u>	Type <u>PVC</u> Dia. <u>1 1/2</u> in.	
<u>CLAY + SAND mix</u>			<u>15</u>	<u>22</u>	Slot/gauze <u>1085</u> Length <u>40</u>	
<u>CLAY BR.</u>			<u>22</u>	<u>25</u>	Set between <u>100</u> ft. and <u>140</u> ft.	
<u>SAND - MEDIUM</u>			<u>25</u>	<u>32</u>	Gravel pack? <u>yes</u> Size range of material <u>1/4"</u>	
<u>CLAY GREEN</u>			<u>32</u>	<u>34</u>	11. Static water level: <u>41</u> ft. below land surface Date <u>5-4-77</u>	
<u>CLAY BLUE</u>			<u>34</u>	<u>50</u>	12. Pumping level below land surfaces:	
<u>SAND MED-to COARSE</u>			<u>50</u>	<u>68</u>	<u>41</u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m.	
<u>CLAY BLUE</u>			<u>68</u>	<u>69</u>	<u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m.	
<u>SAND - COARSE</u>			<u>69</u>	<u>100</u>	Estimated maximum yield <u>1500</u> g.p.m.	
<u>SAND + GRAVEL</u>			<u>100</u>	<u>117</u>	13. Water sample submitted: <u>yes</u> Date <u>4-28-77</u>	
<u>CLAY GREY</u>			<u>117</u>	<u>118</u>	14. Well head completion: <u>18</u> inches above grade	
<u>SAND + GRAVEL</u>			<u>118</u>	<u>138</u>	15. Well grouted? <u>yes</u> <u>Puddled clay</u>	
<u>CLAY GREY</u>			<u>138</u>	<u>140</u>	With: <u> </u> Neat cement <u> </u> Bentonite <u> </u> Concrete	
					Depth: From <u>0</u> ft. to <u>20</u> ft.	
					16. Nearest source of possible contamination: <u>FEED</u>	
					ft. <u>1200</u> Direction <u>West</u> Type <u>LOT</u>	
					Well disinfected upon completion? <u>yes</u> <u>X</u> No	
					17. Pump: <u>Not installed</u>	
					Manufacturer's name <u>WESTERN LAND CONCRETE</u>	
					Model number <u>8-m</u> HP <u>40</u> Volts <u>480</u>	
					Length of drop pipe <u>110</u> ft. capacity <u>800</u> g.p.m.	
					Type: ☐ Submersible ☒ Turbine	
					☐ Jet ☐ Reciprocating	
					☐ Centrifugal ☐ Other	
18. Elevation:			19. Remarks:		20. Water well contractor's certification:	
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley			<u>EXCELLENT WELL</u>		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.	
					Signature: <u>PETERSON FOR INC</u> Date <u>5-4-77</u>	
					Business name: <u>PETERSON FOR INC</u> License No. <u>138A</u>	
					Address: <u>Box 150 LINCOLN, KS</u>	
					Signed: <u>William Peterson</u> Date <u>5-4-77</u>	
					Authorized representative	