


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

County HARVEY		Fraction SE 1/4 NE 1/4 SE 1/4		Section number 34		Township number 24		Range number 2	
1. Location of well:		2. Distance and direction from nearest town or city: 6 mi S AND 1 mi W of				3. Owner of well: RICHARD BECKER			
Street address of well location if in city: HALSTEAD, KS		R.R. or street: R.R.				City, state, zip code: HALSTEAD, KS. 67056			
4. Locate with "X" in section below:		Sketch map:				6. Bore hole dia. 130 in. Completion date 10-4-98 Well depth 125 ft.			
						7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
BROWN SAND (FINE)		6		6		9. Casing: Material TRANSITE Height: above or below Threaded ☐ Welded ☐ Surface 16 in. RMP ☐ PVC ☐ Weight 32 lbs./ft. Dia. 16 in. to 60 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. 1751N			
GRAY CLAY		6		16		10. Screen: Manufacturer's name AURORA TILE COMPANY Type TRANSITE Dia. 16" 1/2 Slot/gauze 1/8 Length 65 ft Set between 60 ft. and 125 ft. ft. and ☐ ft. Gravel pack? YES Size range of material 1/4 in			
BROWN MEDIUM COURSE SAND		16		33		11. Static water level: ☐ ft. below land surface Date ☐ mo./day/yr. 6			
MEDIUM GRAY SAND		33		55		12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1300 g.p.m.			
FINE to MEDIUM SAND		55		84		13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.			
GRAY CLAY		84		92		14. Well head completion: ☐ Pitless adapter 16 Inches above grade			
MEDIUM SANDS		92		121		15. Well grouted? YES PUDDLE CLAY With: ☐ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 20 ft.			
GRAY CLAY		121		125		16. Nearest source of possible contamination: NONE WITHIN ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No			
						17. Pump: Not installed Manufacturer's name WESTERN LANK PUMPS Model number ☐ HP 30 Volts 480 Length of drop pipe 60 ft. capacity 1200 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			
						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PETERSON IRRIGATION 138 Business name Box 50 Lindenberg KS License No. ☐ Address Mike Peterson '11-3-78 Signed ☐ Authorized representative Date			
18. Elevation:		19. Remarks:							
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley									