


1) LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Harvey		NW 1/4 NW 1/4 NW 1/4		16		T 24 S		R 2 EW	
Distance and direction from nearest town or city street address of well if located within city?									
Approximately 2 miles south and 2 1/2 miles west of Halstead									
2) WATER WELL OWNER:		City of Wichita							
RR#, St. Address, Box # :		455 N. Main							
City, State, ZIP Code :		Wichita, KS 67202							
		Board of Agriculture, Division of Water Resources							
		Application Number: HV-006							
3) LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4) DEPTH OF COMPLETED WELL: 209 ft. ELEVATION: Unknown							
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL . 37.7 . . . ft. below land surface measured on mo/day/yr 9/22/98							
		Pump test data: Well water was not ch'd. ft. after hours pumping gpm							
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter . 42 . . . in. to . 215 . . . ft., and in. to ft.							
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well							
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)							
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well							
		Was a chemical/bacteriological sample submitted to Department? Yes No . X; If yes, mo/day/yr sample was submitted							
		Water Well Disinfected? Yes X No							
5) TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped							
1 Steel 3 RMP (SR)		6 Asbestos-Cement 9 Other (specify below) Welded X							
2 PVC 4 ABS		7 Fiberglass Threaded							
Blank casing diameter . 18 . . . in. to . 124 . . . ft., Dia in. to ft., Dia in. to ft.									
Casing height above land surface . 12 . . . in., weight . 70.59 . . . lbs./ft. Wall thickness or gauge No. . 375 . . .									
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement							
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)									
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)							
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes									
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)									
SCREEN-PERFORATED INTERVALS: From . 124 . . . ft. to . 129 . . . tight wind . ft., From . 156 . . . ft. to . 181 . . . tight wind . ft.									
		From . 149 . . . ft. to . 156 . . . tight wind . ft., From . 194 . . . ft. to . 203 . . . tight wind . ft.							
GRAVEL PACK INTERVALS: From . 20 . . . ft. to . 215 . . . ft., From ft. to ft.									
		From ft. to ft., From ft. to ft.							
6) GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other									
Grout Intervals: From . 0 . . . ft. to . 20 . . . ft., From ft. to ft., From ft. to ft.									
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well							
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage None known									
Direction from well?		How many feet?							
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS X				
0	4	Topsoil			coarse				
4	11	Clay, brown	181	193	Clay, gray, green				
11	18	Sand and gravel, fine, medium	193	195	Sand and gravel with clay				
18	30	Clay, brown and gray	195	204	Sand and gravel, fine, medium				
30	54	Clay, gray	204	215	Clay, brown				
54	62	Sand and gravel, fine, medium							
62	81	Clay, gray							
81	107	Sand and gravel, fine, medium, coarse							
107	115	Clay, gray and green							
115	123	Sand and gravel, fine, medium							
123	134	Clay, green							
134	153	Sand and gravel, fine, medium							
153	157	Clay, green							
157	181	Sand and gravel, fine, medium,							
7) CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 9/22/98 and this record is true to the best of my knowledge and belief, Kansas									
Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 10/6/98									
under the business name of Clarke Well & Equipment, Inc. by (signature)									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									