

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Harvey		SE 1/4 SW 1/4 SE 1/4		21		T 24 S		R 2 E W	
Distance and direction from nearest town or city street address of well if located within city? Approximately 1 1/4 miles west and 4 miles south of Halstead									
2 WATER WELL OWNER: City of Wichita RR#, St. Address, Box # : 455 N. Main City, State, ZIP Code : Wichita, KS 67202 Board of Agriculture, Division of Water Resources Application Number:									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 92 ft. ELEVATION: unknown							
N 1 Mile W E S X		Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft.							
		WELL'S STATIC WATER LEVEL not checked ft. below land surface measured on mo/day/yr							
		Pump test data: Well water was not checked ft. after hours pumping gpm							
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter 6 in. to 170 ft., and in. to ft.							
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Index Well							
		Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No ☒							
5 TYPE OF BLANK CASING USED:									
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped									
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded									
Blank casing diameter 2 in. to 70 ft., Dia in. to ft., Dia in. to ft.									
Casing height above land surface 24 in., weight .96 lbs./ft. Wall thickness or gauge No .218									
TYPE OF SCREEN OR PERFORATION MATERIAL:									
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement									
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)									
SCREEN OR PERFORATION OPENINGS ARE:									
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)									
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes									
SCREEN-PERFORATED INTERVALS: From 70 ft. to 90 ft., From ft. to ft.									
GRAVEL PACK INTERVALS: From 61 ft. to 96 ft., From ft. to ft.									
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0 2 Topsoil									
2 7 Clay, gray, dark									
7 22 Clay, gray, sandy									
22 35 Sand, fine, very fine									
35 37 Clay, gray-green									
37 95 Sand and gravel, coarse, medium, fine									
95 102 Clay, green and gray									
102 106 Clay, tan and gray									
106 111 Sand and gravel, medium, fine									
111 131 Clay, green and tan									
131 142 Clay, dark gray									
142 164 Clay, dark green									
164 170 Shale, black, hard									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug									
Grout Intervals: From 0 ft. to 54 ft., From ft. to ft., From 54 ft. to 61 ft.									
What is the nearest source of possible contamination:									
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)									
13 Insecticide storage None known									
Direction from well? How many feet?									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-2-01 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 8-23-01 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.									