

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Harvey	SW $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$	14	T 24 S	R 2 E/W

Distance and direction from nearest town or city street address of well if located within city?

2 3/4 miles South of Halstead, KS

2 WATER WELL OWNER:	John Stutzman	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	7415 S. Hertzler Rd.	Application Number: 15,803
City, State, ZIP Code :	Halstead, KS 67056	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 79 ft. ELEVATION:
--	--

Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft.

WELL'S STATIC WATER LEVEL **23** ft. below land surface measured on mo/day/yr **6-2-03**

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield **800** gpm: Well water was ft. after hours pumping gpm

WELL WATER TO BE USED AS:

1 Domestic	3 Feedlot	5 Public water supply	8 Air conditioning	11 Injection well
☒ Irrigation	4 Industrial	6 Oil field water supply	9 Dewatering	12 Other (Specify below)
	7 Domestic (lawn & garden)	10 Monitoring well		

Was a chemical/bacteriological sample submitted to Department? Yes No ☒; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes ☒ No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued ☒ Clamped
☒ 1 Steel	3 RMP (SR)	9 Other (specify below)	Welded
☒ 2 PVC	4 ABS		Threaded
Blank casing diameter 1.6 in. to 4.9 ft., Dia in. to ft., Dia in. to ft.	6 Asbestos-Cement		
Casing height above land surface 1.2 in., weight 16.15 lbs./ft. Wall thickness or guage No. 500	7 Fiberglass		
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless Steel	5 Fiberglass	☒ 7 PVC
2 Brass	4 Galvanized Steel	6 Concrete tile	8 RMP (SR)
			9 ABS
			10 Asbestos-Cement
			11 Other (Specify)
			12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:	5 Guazed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	☒ 3 Mill slot	9 Drilled holes	
2 Louvered shutter	4 Key punched	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 4.9 ft. to 7.9 ft., From ft. to ft.			
GRAVEL PACK INTERVALS: From 2.2 ft. to 7.9 ft., From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	☒ 2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From 2 ft. to 22 ft., From ft. to ft., From ft. to ft.				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	☒ Other (specify below)
			13 Insecticide storage	Old IRR. well
Direction from well? West			How many feet? 99	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	Topsoil			
4	35	Sand, fine to medium			
35	40	Clay, gray with medium sand			
40	47	Sand, fine to medium			
47	51	Sand, medium to coarse			
51	55	Clay, gray with medium sand			
55	60	Sand, fine to medium			
60	68	Sand, medium to coarse			
68	75	Sand, fine			
75	79	Clay, gray			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6/02/03 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No 138 This Water Well Record was completed on (mo/day/yr) 6/2/03 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i>
--