

KSA 82a-1212

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB14S	
LOCATION: NW ¼ NW ¼ NW ¼ NW ¼, 16-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 58' 10.9"	
LONGITUDE: 097° 33' 15.6"	
FOOTAGES: 5012 feet from the South section line and 4953 feet from the East section line.	
DATE: 10-23-09	DRILLED BY: Dave

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	16	Clay
16	20	Medium and coarse sand
20	37	Clay
37	43	Fine gravel
43	50	Clay

Well Depth: 45'
Bore Hole Dia: 6"

Plain casing: 35' of 2"
Perf. casing: 10' of 2"

Gravel pack from 29' to 45'
Bentonite from 0' to 29'

dh