

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB26D	
LOCATION: SW ¼ NW ¼ SW ¼ NW ¼, 22-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 57' 4.0"	
LONGITUDE: 097° 32' 11.7"	
FOOTAGES: 3533 from the South section line and 5092 feet from the East section line.	
DATE: 10-27-09	DRILLED BY: Dave

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	7	Medium sand
7	10	Clay
10	20	Fine gravel
20	38	Medium gravel
38	39	Clay
39	58	Fine gravel
58	60	Clay
60	84	Medium sand
84	86	Clay
86	94	Medium sand
94	95	Clay
95	98	Medium sand
98	140	Clay
140	148	Coarse sand with clay seams
148	152	Fine sand
152	156	Clay
156	163	Medium sand
163	166	Clay
166	180	Medium sand
180	196	Coarse sand
196	199	Clay
199	210	Shale

Well Depth: 195'
Bore Hole Dia: 6"

Plain casing: 175' of 2"
Perf. casing: 20' of 2" slot size: .020"

Gravel pack from 168' to 195'
Bentonite from 0' to 168'