

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB19D	
LOCATION: SE ¼ SE ¼ SE ¼ SW ¼, 22-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 56' 30.9"	
LONGITUDE: 097° 31' 42.6"	
FOOTAGES: 171 feet from the South section line and 2812 feet from the East section line.	
DATE: 10-27-09	DRILLED BY: Dave

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	18	Clay
18	23	Medium sand
23	37	Medium gravel
37	44	Clay
44	60	Medium and coarse sand
60	65	Coarse sand
65	83	Medium sand
83	123	Sandy clay
123	126	Medium sand
126	127	Clay
127	139	Medium sand
139	140	Clay
140	156	Medium sand
156	173	Sandy clay
173	191	Medium gravel
191	194	Clay
194	200	Shale

Well Depth: 188'
Bore Hole Dia: 6"

Plain casing: 168' of 2"
Perf. casing: 20' of 2"

slot size: .020"

Gravel pack from 162' to 188'
Bentonite from 0' to 162'