

Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MW1D	
LOCATION: SW ¼ SW ¼ NW ¼ SW ¼, 5-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 59' 19.7"	
LONGITUDE: 097° 34' 25.8"	
FOOTAGES: 1342 feet from the South section line and 5314 feet from the East section line.	
DATE: 11-10-09	DRILLED BY: CL

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	15	Clay
15	20	Fine and medium sand
20	60	Fine, medium and coarse sand and fine gravel
60	80	Fine, medium and coarse sand and fine and medium gravel
80	96	Fine, medium and coarse sand
96	102	Blue clay
102	110	Fine, medium and coarse sand
110	111	Clay
111	115	Fine, medium and coarse sand
115	117	Clay
117	125	Fine, medium and coarse sand
125	127	Clay
127	129	Fine, medium and coarse sand
129	137	Clay
137	140	Fine, medium and coarse sand
140	160	Fine, medium and coarse sand and fine gravel
160	209	Fine, medium and coarse sand
209	214	Clay
214	220	Fine, medium and coarse sand
220	259	Fine, medium and coarse sand and fine gravel
259	268	Shale

Well Depth: 260'
Bore Hole Dia: 6"

Plain casing: 240' of 2"
Perf. casing: 20' of 2" slot size: .020"

Gravel pack from 230' to 260'
Bentonite from 0' to 230'