

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Harvey

Location listed as:

Section-Township-Range: 35-35S-2W

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): SE SE SE NE

Location changed to:

35-24S-2W

SE SE SE NE

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

verification method: Latitude & longitude, KGS' "LEO" conversion tool,
written description given on second page, and mapping tool &
aerial photo on KGS website. initials: DR date: 12/15/2009

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726

to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

1 LOCATION OF WATER WELL:

County: Harvey

Fraction

SE ¼ SE ¼ SE ¼ NE ¼

Section Number

35

Township No.

T 35 S

Range Number

R 2 ☐ E ☒ WStreet/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐.

1/2 mile south of intersection SW 96th St. and 135th St. on the west side of 135th St.

2 WATER WELL OWNER:

City of Wichita

RR#, Street Address, Box #: 455 North Main Street

City, State, ZIP Code : Wichita, KS 67202

Global Positioning System (GPS) information:

Latitude: 37° 55' 13.6" (in decimal degrees)

Longitude: 097° 30' 4.6" (in decimal degrees)


Elevation:

Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27

Collection Method:

☒ GPS unit (Make/Model: Garmin)☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land SurveyEst. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m

3 LOCATE WELL WITH AN "X" IN SECTION BOX:



4 DEPTH OF COMPLETED WELL 45 ft.

Depth(s) Groundwater Encountered (1) 18.6 ft. (2) ft. (3) ft.

WELL'S STATIC WATER LEVEL 18.6 ft. below land surface measured on mo/day/yr. 10/28/09

Pump test data: Well water was ft. after hours pumping gpm

EST. YIELD gpm. Well water was ft. after hours pumping gpm

Bore Hole Diameter 6 in. to 46 ft., and in. to ft.

WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☒ Other (Specify below)☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well ☐ ObservationWas a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No

If yes, mo/day/yr sample was submitted

Water well disinfected? ☐ Yes ☒ No

5 TYPE OF CASING USED:

☐ Steel ☒ PVC ☐ OtherCASING JOINTS: ☒ Clamped ☐ Welded ☒ Threaded

Casing diameter 2 in. to 35 ft., Diameter in. to ft.

Casing height above land surface 24 in., Weight 703 lbs./ft., Wall thickness or gauge No. 154

TYPE OF SCREEN OR PERFORATION MATERIAL:

☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify)☐ Brass ☐ Galvanized Steel ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole)☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify)

SCREEN-PERFORATED INTERVALS: From 35 ft. to 45 ft., From ft. to ft.

GRAVEL PACK INTERVALS: From 30 ft. to 45 ft., From ft. to ft.

From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other

Grout Intervals: From 0 ft. to 30 ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:

☒ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below)☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well

Direction from well Distance from well Over 1000 feet

FROM TO LITHOLOGIC LOG FROM TO LITHO. LOG (cont.) or PLUGGING INTERVALS

Log attached

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:

This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged

under my jurisdiction and was completed on (mo/day/year) 10/28/2009 and this record is true to the best of my knowledge and belief.

Kansas Water Well Contractor's License No. 755 This Water Well Record was completed on (mo/day/year) 11/11/2009

under the business name of Sargent Drilling by (signature)

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies

(white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367.

Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at

<http://www.kdheks.gov/waterwell/index.html>

KSA 82a-1212

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB23S	
LOCATION: SE ¼ SE ¼ SE ¼ NE ¼, 35-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 55' 13.6"	
LONGITUDE: 097° 30' 04.6"	
FOOTAGES: 2968 feet from the South section line and 231 feet from the East section line.	
DATE: 10-28-09	DRILLED BY: CL

SWL:

PWL:

from feet - to feet

0	15	Topsoil and clay
15	20	Fine, medium and coarse sand
20	46	Fine, medium and coarse sand and fine and medium gravel

Well Depth: 45'

Bore Hole Dia: 6"

Plain casing: 35' of 2"

Perf. casing: 10' of 2"

slot size: .020"

Gravel pack from 30' to 45'

Bentonite from 0' to 30'

dh