

Form WWC-5

SA 82a-1212

Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB59D	
LOCATION: SE ¼ SE ¼ SW ¼ SW ¼, 16-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 57' 23.2"	
LONGITUDE: -97° 33' 04.9"	
FOOTAGES: 189 feet from the South section line and 4065 feet from the East section line.	
DATE: 11/9/009	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL: 26'

PWL:

GPM:

<u>from feet</u>	<u>- to feet</u>	
0	3	Top soil
3	10	Sandy clay and fine sand
10	20	Sandy clay and fine sand
20	60	Coarse sand to fine gravel
60	90	Fine to coarse sand
90	110	Fine to medium sand
110	185	Sandy clay
185	200	Fine to coarse sand
200	240	Fine to coarse sand and traces of fine gravel
240	249	Gray shale

Well Information:

Well depth: 240'
Plain casing: 220'
Perf. Set: 220-240'

Bore hole: 6"
Perf. casing: 20'
Gravel: 215-240'

Casing size: 2"
Slot size: .020"
Grout: 0-215'