

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Harvey

Location listed as:

Section-Township-Range: 17-245-2 WFraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): SE SE NE NE

Location changed to:

29-245-2 WSE SE NE NE

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

verification method: Latitude & longitude, KGS' "LEO" conversion tool,
written description, location given on attached page, and
mapping tool on KGS website. initials: DRF date: 2/28/2011

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

R 2 ☐ E ☒ W

Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m

Check: ☒ White Copy. ☐ Blue Copy. ☐ Pink Copy.

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB61D	
LOCATION: SE ¼ SE ¼ NE ¼ NE ¼, 29-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 56' 17.1"	
LONGITUDE: -97° 33' 21.2"	
FOOTAGES: 4084 feet from the South section line and 116' from the East section line.	
DATE: 11/11/09	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL: 22'

PWL:

GPM:

<u>from feet</u>	<u>to feet</u>	
0	5	Top soil and clay
5	10	Clay
10	20	Sandy clay
20	30	Sandy clay to fine sand
30	35	Fine sand
35	50	Medium gravel
50	55	Fine sand
55	80	Sandy clay
80	85	Fine gravel
85	110	Medium gravel
110	120	Fine sand
120	160	Sandy clay
160	165	Fine sand
165	170	Sandy clay and fine sand
170	190	Sandy clay
190	195	Clay
195	200	Sandy clay and fine gravel
200	220	Clay
220	240	Sandy clay
240	250	Fine gravel and sandy clay
250	255	Fine gravel and shale
255	260	Shale

Well Information:

Well depth: 252'
Plain casing: 232'
Perf. Set: 232-252'

Bore hole: 6"
Perf. casing: 20'
Gravel: 227'-252'

Casing size: 2"
Slot size:
Grout: 0-227'