
Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB 13D	
LOCATION: NW ¼ NW ¼ NW ¼ NE ¼, 17-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 58' 11.3"	
LONGITUDE: 097° 33' 50.3"	
FOOTAGES: 5054 feet from the South section line and 2485 feet from the East section line.	
DATE: 10/29/09	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL: 41'
PWL:
GPM:

<u>from feet</u>	<u>- to feet</u>	
0	8	Top soil and clay
8	23	Sandy clay and fine sand
23	40	Coarse sand to fine gravel
40	60	Coarse sand to fine gravel with traces of sandy clay
60	100	Sandy clay and fine to medium sand
100	120	Fine to medium sand with thin sandy clay strips
120	140	Andy clay and fine sand
140	180	Sandy clay
180	200	Sandy clay and fine sand
200	220	Fine to coarse sand and traces of fine gravel
220	240	Fine to coarse sand and fine gravel
240	260	Fine to coarse sand and fine gravel with traces of shale
260	270	Black shale

Well Information:

Well depth: 258'
Plain casing: 238'
Perf. Set: 238'-268'

Bore hole: 6"
Perf. casing: 20'
Gravel: 243-258'

Casing size: 2"
Slot size:
Grout: 0-243'