
Check: ☒ White Conv ☐ Blue Conv ☐ Pink Conv

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB 13S	
LOCATION: NW ¼ NW ¼ NW ¼ NE ¼, 17-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 58' 11.3"	
LONGITUDE: 097° 33' 50.4"	
FOOTAGES: 5054 feet from the South section line and 2493 feet from the East section line.	
DATE: 10/29/09	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL: 26'

PWL:

GPM:

from feet - to feet

0	8	Top soil and clay
8	23	Sandy clay and fine sand
23	40	Coarse sand to fine gravel
40	60	Coarse sand to fine gravel with traces of sandy clay

Well Information:

Well depth: 45'
Plain casing: 35'
Perf. Set: 35'-45'

Bore hole: 6"
Perf. casing: 10'
Gravel: 30-45'

Casing size: 2"
Slot size:
Grout: 0-30'