

Division of Water Resources App. No.

KSA 82a-1212

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR59 Supply Well	
LOCATION: SE ¼ SE ¼ SW ¼ SW ¼, 16-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 57' 22.6"	
LONGITUDE: 097° 33' 4.9"	
FOOTAGES:	
DATE: 2-1-10	DRILLED BY:

SWL: 20'
PWL: 300 @ 61'

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	8	Clay
8	20	Coarse sand
20	32	Fine gravel
32	35	Clay
35	54	Fine gravel
54	60	Clay
60	80	Gravel

Well Depth: 80'
Bore Hole Dia: 10"

Plain casing: 40' of 6"
Perf. casing: 40' of 6" slot size: .025"

Gravel pack from 25' to 80'
Hole plug` from 0' to 25'

dh