
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR58	
LOCATION: NE ¼ NE ¼ NE ¼, 19-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 57' 20.0"	
LONGITUDE: 097° 34' 28.7"	
FOOTAGES: 5136 feet from the South section line and 146 feet from the East section line.	
DATE: 10-20-09	DRILLED BY: Dave

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	6	Medium sand
6	20	Sandy clay
20	32	Clay
32	40	Fine gravel
40	50	Medium gravel
50	52	Clay
52	80	Fine gravel
80	99	Medium sand
99	100	Clay
100	103	Medium sand
103	124	Clay
124	150	Medium sand
150	160	Clay

dh

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

MR58 – Section 5

	FROM	TO
Steel Recharge Casing – 4” - .337” wall Grade B	0’	50’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	0’	58’
Stainless Steel Casing – 18” - .500” wall ASTM A312	58’	63’
Stainless Steel Screen – 18” - .500” wall .090 slot 304 Stainless	63’	95’
Stainless Steel Casing – 18” - .500” wall ASTM A312	95’	100’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	100’	120’
Stainless Steel Casing – 18” - .500” wall ASTM A312	120’	125’
Stainless Steel Screen – 18” - .500” wall .090 slot 304 Stainless	125’	150’
Stainless Steel Casing – 18” - .500” wall ASTM A312	150’	155’