
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB58D	
LOCATION: NE ¼ NE ¼ NE ¼ NE ¼, 19-T24S-R2W, Garvey Co., KS	
LATITUDE: 37° 57' 19.5"	
LONGITUDE: 097° 34' 28.5"	
FOOTAGES: 5085 feet North of the South line and 130 feet West of East line.	
DATE: 2-2-10	DRILLED BY: CL

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	5	Topsoil
5	10	Fine, medium and coarse sand
10	20	Sandy clay
20	80	Fine, medium and coarse sand and fine gravel
80	100	Fine, medium and coarse sand with thin clay strips
100	125	Clay
125	150	Fine, medium and coarse sand
150	160	Clay and cobbles

Well Depth: 147'
Bore Hole Dia: 7"

Plain casing: 127' of 2"
Perf. casing: 20' of 2" slot size: .020"

Gravel pack from 122' to 147'
Bentonite from 0' to 122'

dh