
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MW5S	
LOCATION: SW ¼ SW ¼ SE ¼ SE ¼, 22-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 56' 29.4"	
LONGITUDE: 097° 31' 23.3"	
FOOTAGES: 9' from the South section line and 1268 feet from the East section line.	
DATE: 2-2-10	DRILLED BY: DG

SWL: 17.4
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil and clay
2	17	Clay
17	60	Fine gravel

Well Depth: 45'
Bore Hole Dia: 6"

Plain casing: 35' of 2"
Perf. casing: 10' of 2"
Casing

slot size: .020"

Gravel pack from 30' to 45'
Bentonite from 0' to 30'

dh