

Division of Water Resources App. No.

[illegible]

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 627
263 South 23rd Street

Broken Bow, Nebraska
68822

Phone: (308) 872-5125
FAX (308) 872-3050

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR61 Supply Well	
LOCATION: SE ¼ SE ¼ NE ¼, 29-T24S-R02W, Harvey Co., KS	
LATITUDE: 37° 56' 16.7"	
LONGITUDE: 097° 33' 20.6"	
FOOTAGES: 4033 feet from the South section line and 68 feet from the East section line.	
DATE: 2-3-10	DRILLED BY: DG

SWL: 22
PWL: 300 @ 62

<u>from feet</u>	<u>- to feet</u>	
0	2	Top Soil
2	22	Clay
22	40	Coarse Sand / Fine Gravel
40	52	Coarse Sand
52	72	Clay
72	80	Gravel

Well Information:

Well Depth: 80'
Plain casing: 40' of 6"
Perf. Set: 40 to 80'

Bore Hole Dia: "
Perf. casing: 40' of 6"
Gravel: 20' to 80'

Casing size: 6"
Slot size: .025"
Hole Plug: 0' to 20'

mp