
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR61	
LOCATION: SE ¼ SE ¼ NE ¼ NE ¼, 29-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 56' 17.3"	
LONGITUDE: 097° 33' 21.7"	
FOOTAGES: 4094' North of the South line and 156' West of the East line.	
DATE: 10-13-09	DRILLED BY:

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	20	Topsoil and clay
20	52	Fine, medium and coarse sand and fine and medium gravel
52	60	Blue clay
60	65	Clay
65	80	Fine, medium and coarse sand and fine and medium gravel
80	89	Fine, medium and coarse sand and fine, medium and coarse gravel
89	105	Clay
105	120	Fine, medium and coarse sand
120	126	Fine, medium and coarse sand and fine gravel
126	127	Clay
127	137	Fine, medium and coarse sand
137	140	Clay
140	156	Fine, medium and coarse sand
156	166	Clay
166	176	Fine, medium and coarse sand and clay strips
176	185	Clay
185	237	Fine, medium and coarse sand and clay layers
237	251	Fine, medium and coarse sand and fine gravel
251	260	Shale

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

MR61 – Section 5

	FROM	TO
Steel Recharge Casing – 4" - .337" wall Grade B	0'	64'
Carbon Steel Casing – 18" - .500" wall A53 Grade B	0'	67'
Stainless Steel Casing – 18" - .500" wall ASTM A312	67'	72'
Stainless Steel Screen – 18" - .500" wall .090 slot 304 Stainless	72'	89'
Stainless Steel Casing – 18" - .500" wall ASTM A312	89'	105'
Stainless Steel Screen – 18" - .500" wall .050 slot 304 Stainless	105'	155'
Stainless Steel Casing – 18" - .500" wall ASTM A312	155'	160'
Carbon Steel Casing – 18" - .500" wall A53 Grade B	160'	232'
Stainless Steel Casing – 18" - .500" wall ASTM A312	232'	237'
Stainless Steel Screen – 18" - .500" wall .050 slot 304 Stainless	237'	249'
Stainless Steel Casing – 18" - .500" wall ASTM A312	249'	254'