

--

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR60	
LOCATION: NW ¼ NW ¼ NW ¼ SW ¼, Harvey Co. KS	
LATITUDE: 37° 56' 53.3"	
LONGITUDE: 097° 33' 18.1"	
FOOTAGES: 2441' from the South section line and 5138' from the East section line.	
DATE: 10-19-09	DRILLED BY: CL

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	20	Topsoil and clay
20	23	Sandy clay
23	76	Fine, medium and coarse sand and fine gravel
76	77	Clay
77	82	Fine, medium and coarse sand and fine gravel
82	84	Clay
84	100	Fine, medium and coarse sand
100	109	Fine, medium and coarse sand and fine gravel
109	185	Clay
185	195	Fine, medium and coarse sand
195	200	Clay
200	220	Fine, medium and coarse sand and clay layers
220	247	Fine, medium and coarse sand and fine gravel
247	260	Clay

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

MR60 – Section 5

	FROM	TO
Steel Recharge Casing – 4” .337” wall Grade B	0’	57’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	0’	60’
Stainless Steel Casing – 18” - .500” wall ASTM A312	60’	65’
Stainless Steel Screen – 18” - .500” wall .050” slot 304 Stainless	65’	110’
Stainless Steel Casing - 18” - .500” wall ASTM A212	110’	115’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	115’	182’
Stainless Steel Casing – 18” - .500” wall ASTM A312	182’	187’
Stainless Steel Screen – 18” - .500” wall .050” slot 304 Stainless	187’	244’
Stainless Steel Casing – 18” - .500” wall ASTM A312	244’	249’