
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR59	
LOCATION: SE ¼ SE ¼ SW ¼ SW ¼, 16-T24S-T2W, Harvey Co., KS	
LATITUDE: 37° 57' 22.5"	
LONGITUDE: 097° 33' 4.5"	
FOOTAGES: 119 feet from the South section line and 4033 feet from the East section line.	
DATE: 10-20-09	DRILLED BY: Dave

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	9	Clay
9	20	Fine gravel
20	40	Medium gravel
40	59	Fine gravel
59	63	Clay
63	80	Fine gravel with clay stringers
80	115	Medium sand
115	123	Clay
123	128	Coarse sand
128	130	Clay
130	133	Coarse sand
133	137	Clay
137	144	Coarse sand
144	183	Clay
183	238	Coarse sand
238	240	Clay
240	252	Shale

dh

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

MR59 – Section 5

	FROM	TO
Steel Recharge Casing – 4” .337” wall Grade B	0’	60’
Carbon Steel Casing - 18” - .500” wall A53 Grade B	0’	180’
Stainless Steel Casing – 18” - .500” wall ASTM A312	180’	185’
Stainless Steel Screen – 18” - .500” wall .090” slot 304 Stainless	185’	235’
Stainless Steel Casing – 18” - .500” wall ASTM A312	235’	240’