

OB26D RD Form WWC-5

Division of Water Resources App. No.

[illegible]

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB26D	
LOCATION: SW ¼ NW ¼ SW ¼ NW ¼, 22-T24S-R2W, Harvey Co., KS	
LATITUDE: 37° 57' 03.8"	
LONGITUDE: 097° 32' 12.9"	
FOOTAGES: 3513 feet North of the South section line and 5189 feet West of the East section line.	
DATE: 2-2-10	DRILLED BY: CL

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	20	Fine, medium and coarse sand and fine gravel
20	77	Fine, medium and coarse sand and fine and medium gravel
77	80	Blue clay
80	100	Clay and sandy clay
100	152	Clay
152	170	Fine, medium and coarse sand and clay layers
170	195	Fine, medium and coarse sand
195	199	Clay
199	202	Fine, medium and coarse sand
202	210	Shale

Well Depth: 200'
Bore Hole Dia: 7"

Plain casing: 180' of 2"
Perf. casing: 20' of 2" slot size: .020"

Gravel pack from 175' to 200'
Bentonite from 0' to 175'

dh