

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Harvey Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ . One mile south and two miles west of Halstead, KS		Fraction SE ¼ SE ¼ SW ¼ ¼		Section Number 4		Township No. T 24 S		Range Number R 2 ☐ E ☒ W																																																													
2 WATER WELL OWNER: Eddie Weber RR#, Street Address, Box #: 7 Leslie Lane City, State, ZIP Code : Halstead, KS 67056		Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																			
3 LOCATE WELL WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 95 ft. Depth(s) Groundwater Encountered (1) 34 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 34 ft. below land surface measured on mo/day/yr. 10/15/10 Pump test data: Well water was ft. after hours pumping gpm EST. YIELD 800 gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter 30 in. to 95 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No																																																																			
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 55 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 12 in., Weight 16 lbs./ft., Wall thickness or gauge No. Sch40 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 55 ft. to 95 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 95 ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																					
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 3 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well irrigation well Direction from well northeast Distance from well 1/4 mile																																																																					
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;">FROM</th> <th style="width: 10%;">TO</th> <th style="width: 40%;">LITHOLOGIC LOG</th> <th style="width: 10%;">FROM</th> <th style="width: 10%;">TO</th> <th style="width: 20%;">LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>10</td> <td>Top Soil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>10</td> <td>40</td> <td>Sand</td> <td></td> <td></td> <td></td> </tr> <tr> <td>35</td> <td>55</td> <td>Clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>55</td> <td>65</td> <td>Fine to Med. Sand with clay streaks</td> <td></td> <td></td> <td></td> </tr> <tr> <td>65</td> <td>80</td> <td>Medium Sand with clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>80</td> <td>90</td> <td>Medium to Coarse Sand</td> <td></td> <td></td> <td></td> </tr> <tr> <td>90</td> <td>95</td> <td>Clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	10	Top Soil				10	40	Sand				35	55	Clay				55	65	Fine to Med. Sand with clay streaks				65	80	Medium Sand with clay				80	90	Medium to Coarse Sand				90	95	Clay															
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																
0	10	Top Soil																																																																			
10	40	Sand																																																																			
35	55	Clay																																																																			
55	65	Fine to Med. Sand with clay streaks																																																																			
65	80	Medium Sand with clay																																																																			
80	90	Medium to Coarse Sand																																																																			
90	95	Clay																																																																			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 10/15/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 238 This Water Well Record was completed on (mo/day/year) 10/18/10 under the business name of Premier Pump and Well Service, Inc. by (signature) Patrick A. Newman																																																																					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																					