

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

28144

1 LOCATION OF WATER WELL: County: Harvey Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 2 miles west & 6 miles south of Halstead, KS	Fraction 1/4 1/4 NC 1/4 NW 1/4	Section Number 33	Township No. T 24 S	Range Number R 2 ☐ E ☒ W
---	--	----------------------	------------------------	--

Global Positioning System (GPS) information:
 Latitude: (in decimal degrees)
 Longitude: (in decimal degrees)
 Elevation:
 Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27
 Collection Method:
☐ GPS unit (Make/Model:)
☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey
 Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m

2 WATER WELL OWNER: Kenneth Krauss RR#, Street Address, Box #: 9924 S. Sprinlake Rd. City, State, ZIP Code : Sedwick, KS 67135	3 LOCATE WELL WITH AN "X" IN SECTION BOX:
---	--

4 DEPTH OF COMPLETED WELL 135 ft.
 Depth(s) Groundwater Encountered (1) 22 ft. (2) ft. (3) ft.
 WELL'S STATIC WATER LEVEL 22 ft. below land surface measured on mo/day/yr. 2/6/2013
 Pump test data: Well water was ft. after hours pumping gpm
 EST. YIELD 655 gpm. Well water was ft. after hours pumping gpm
 Bore Hole Diameter in. to ft., and in. to ft.
 WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well
☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below)
☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well
 Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No
 If yes, mo/day/yr sample was submitted
 Water well disinfected? ☒ Yes ☐ No

5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other
CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded
 Casing diameter 16 in. to 95 ft., Diameter in. to ft.
 Casing height above land surface 12 in., Weight 16 lbs./ft., Wall thickness or gauge No. SCH40
TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole)
☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify)
SCREEN-PERFORATED INTERVALS: From 95 ft. to 135 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From 20 ft. to 135 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other
 Grout Intervals: From 3 ft. to 20 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination:
☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below)
☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☒ Abandoned water well
☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well
 Direction from well SW Distance from well 25'

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	2	Topsoil	100	117	Sand and gravel
2	15	Clay, Sandy	117	118	Clay, grav
15	22	Clay and Sand mix	118	130	Sand and gravel
22	25	Clay, brown	130	135	Clay, grav
25	32	Medium Sand			
32	34	Clay, green			
34	50	Clay, blue			
50	68	Medium to Coarse Sand			
68	69	Clay, blue			
69	100	Coarse Sand			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 2/6/2013 and this record is true to the best of my knowledge and belief.
 Kansas Water Well Contractor's License No. 238 This Water Well Record was completed on (mo/day/year) 2/15/2013
 under the business name of Premier Pump & Well Service, Inc. by (signature) D. Wiering

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>.