


1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Harvey		NW 1/4 NW 1/4 NW 1/4		16		T 24 S		R 2 EW	
Distance and direction from nearest town or city street address of well if located within city?									
Approximately 2 miles west and 2 miles south of Halstead									
2 WATER WELL OWNER:		Wichita, City of				Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # :		12th Floor, City Building				Application Number:			
City, State, ZIP Code :		455 N. Main Wichita, KS 67202							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 138 ft. ELEVATION: unknown							
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL 48.85 ft. below land surface measured on mo/day/yr 5-5-95							
		Pump test data: Well water was not ch'd. ft. after hours pumping gpm							
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter 9 in. to 160 ft., and in. to ft.							
WELL WATER TO BE USED AS:		5 Public water supply 8 Air conditioning 11 Injection well							
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)									
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well									
Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted									
Water Well Disinfected? Yes X No									
5 TYPE OF BLANK CASING USED:									
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped									
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded									
7 Fiberglass Threaded									
Blank casing diameter 5 in. to 120 ft., Dia. in. to ft., Dia. in. to ft.									
Casing height above land surface 24 in., weight 2.36 lbs./ft. Wall thickness or gauge No. 214									
TYPE OF SCREEN OR PERFORATION MATERIAL:									
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement									
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)									
9 ABS 12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:									
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)									
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes									
7 Torch cut 10 Other (specify)									
SCREEN-PERFORATED INTERVALS:									
From 120 ft. to 136 ft., From ft. to ft.									
From ft. to ft., From ft. to ft.									
GRAVEL PACK INTERVALS:									
From 25 ft. to 110 ft., From ft. to ft.									
From 119 ft. to 140 ft., From ft. to ft.									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug									
Grout Intervals: From 0 ft. to 5 ft., From 5 ft. to 25 ft., From 110 ft. to 119 ft.									
What is the nearest source of possible contamination:									
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)									
13 Insecticide storage None known									
Direction from well? How many feet?									
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0 4 Clay, brown 97 120 Clay, green and blue									
4 8 Clay, gray 120 136 Sand, very fine, medium, loose, clean									
8 12 Clay, tan, sandy									
12 20 Sand and gravel, fine, medium, loose, clean 136 140 Clay, green									
20 28 Clay, pink and green 140 153 Sand and gravel, very fine to fine, loose, clean									
28 33 Sand, very fine, fine, loose, clean 153 160 Clay, gray, hard									
33 43 Sand and gravel, very fine, fine, loose, clean, with clay streaks									
43 69 Sand and gravel, very fine, medium, loose, clean, gray									
69 80 Clay, green, hard, thin sand streaks									
80 97 Sand and gravel, very fine, medium, loose, clean									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-5-95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 5-15-95 under the business name of Clarke Well & Equipment, Inc. by (signature) [Signature]									