

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: MOGEMAN NE 1/4 NE 1/4 NE 1/4 16 T 24 S R 22 *FW* (DRD)

Distance and direction from nearest town or city street address of well if located within city?  
 FROM SPEARVILLE ON 226 - 9 NORTH AND 1 EAST

2 WATER WELL OWNER: BENISH, ANNETTE  
 RRA, St. Address, Box #: 37486 S.E. D RD. Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: SPEARVILLE, KS 67876- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
W			X
SW			NE
SE			

4 DEPTH OF COMPLETED WELL 325 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 74 ft. below land surface measured on mo/day/yr 09/15/10  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 325 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIM CASING JOINTS: CERTA-LOC  
 Blank casing diameter 5 in. to 325 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 160 ft., From 0 ft. to 0 ft.  
 From 280 ft. to 320 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 325 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	01 TOPSOIL			
5	35	37 FIN-COAR SAN 38 SHAL-MED GRA			
35	110	36 BLUE CLAY 16 GRAY CLAY			
110	155	29 SANDSTONE			
155	175	16 GRAY CLAY			
175	190	29 SANDSTONE			
190	280	16 GRAY CLAY 26 RED CLAY			
280	300	29 SANDSTONE			
300	330	29 SANDSTONE 16 GRAY CLAY 19 LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/17/10 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/30/10  
 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Crick*