

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction SW 1/4 SE 1/4 SE 1/4 Section Number 18 Township Number T 24 S Range Number R 23 W  
 COUNTY: HODGEMAN

Distance and direction from nearest town or city street address of well if located within city?  
 FROM JETMORE, KS. - 8 MILES SOUTH ON 283 HIGHWAY 1/2 M. EAST

2 WATER WELL OWNER: DENNIS BRADFORD  
 R.R.#, St. Address, Box #: R.R. #1 - BOX 31-A Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: JETMORE, KS 67854- Application Number:

3 LOCATE WELL'S LOCATION WITH AS "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 105 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 62 ft. below land surface measured on mo/day/yr 07/01/92  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 20 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 10 in. to 105 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 105 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 100 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 35 ft. to 105 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout intervals: From 5 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: LIVESTOCK PENS  
 Direction from well? SOUTH How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	30	LIMESTONE			
30	50	FINE - MED SAND			
50	55	CLAY			
55	62	FINE SAND			
62	65	CLAY			
65	95	MED-COARSE SAND SMALL GRAVEL			
95	97	ROCK LAYERS CLAY			
97	101	BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 07/01/92 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 07/22/92  
 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Jared Cook*