

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NW 1/4 SE 1/4 SE 1/4 Section Number 34 Township Number T 22 24 S Range Number R 23 W
 COUNTY: HODGEMAN

Distance and direction from nearest town or city street address of well if located within city?
 FROM FORD CO. & HODGEMAN LINE - 1 NORTH, 4 EAST & 3/4 SOUTH

2 WATER WELL OWNER: FAGEN, RAYMOND Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: RR 1 Application Number:
 City, State, ZIP code: SPEARVILLE, KS 67876-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 305 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 162 ft. below land surface measured on mo/day/yr 03/23/98
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 20 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 305 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 305 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 220 ft. to 300 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 305 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY BLUE CLAY			
20	40	BLUE CLAY			
40	60	BLUE CLAY GRAY CLAY ROCK LAYERS			
60	80	GRAY CLAY ROCK LAYERS			
80	140	BROWN CLAY BLUE CLAY IN LAYERS			
140	160	GRAY CLAY RED CLAY IN LAYERS			
160	180	SANDSTONE			
180	220	GRAY CLAY SANDSTONE IN LAYERS			
220	280	SANDSTONE			
280	300	SANDSTONE GRAY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 03/24/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 04/13/98 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joseph A. Crist*

RECEIVED

JUN 1 6 1998

BUREAU OF WATER

(Continued) WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NW 1/4 SE 1/4 SE 1/4 Section Number 34 Township Number T 22 S Range Number R 23 W
 COUNTY: HODGEMAN

2 WATER WELL OWNER: FAGEN, RAYMOND Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: RR 1 Application Number:
 City, State, ZIP code: SPEARVILLE, KS 67876-

FROM	TO	LITHOLOGIC LOG
300	340	SANDSTONE GRAY CLAY ROCK LAYERS