

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

DBC

1. Location of well:		County Hodgeman	Fraction SW 1/4 NW 1/4 SE 1/4	Section number 20	Township number T 24 S	Range number R 25 E
2. Distance and direction from nearest town or city: 11 mi. north and 2 1/2 west of Dodge City Street address of well location if in city:				3. Owner of well: Marvin Hampton R.R. or street: City, state, zip code: Dodge City, Kansas 67801		
4. Locate with "X" in section below:		Sketch map:				
5. Type and color of material		From	To			
Surface			0			
Brown caleche clay			3			
Med. sand (dry)			44			
Hard rock and yellow clay			60			
Gray and blue shale with rock layers			73			
Gray shale with some red bed mixed			320			
Good, clean brown sandstone-some purple near bottom			365			
Gray shale			443			
BROCK 60' deep						
TOPO 2563						
60 / 2503 ✓						
CRETACEOUS WELL						
(Use a second sheet if needed)						
6. Bore hole dia. 26 in. Completion date 1-13-76 Well depth 455 ft.						
7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary						
8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other						
9. Casing: Material Metal Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 31 & 36 lbs./ft. Dia. 16 in. to 455 ft. depth Wall thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gauge No. 188 & 219						
10. Screen: Manufacturer's name W.A. Brown Type 10% Free-flow Dia. 16" Stb. gauze 1/8 Length 100' Set between 355 ft. and 455 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack <input checked="" type="checkbox"/> yes Size range of material 1/2 down						
11. Static water level: <input type="checkbox"/> mo./day/yr. 258 ft. below land surface Date 1-3-76						
12. Pumping level below land surfaces: 338 ft. after 4 hrs. pumping 700 g.p.m. 363 ft. after 24 hrs. pumping 700 g.p.m. Estimated maximum yield 850 g.p.m.						
13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date						
14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> <input type="checkbox"/> Inches above grade						
15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.						
16. Nearest source of possible contamination: NA ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No						
17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other						
18. Elevation:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Ace-Hi Int. Inc. 190 Business name License No. Address Dodge City, Kansas Signed Carl G. Jittel Date 1-7-76 Authorized representative				
19. Remarks:						
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

24
 250
 20
 SW
 NW
 SE
 E