

WATER WELL RECORD Form WWC-5 KSA 82A-1212

1 LOCATION OF WATER WELL: COUNTY: 042 HODGEMAN FRACTION SW 1/4 SW 1/4 SW 1/4 SECTION NUMBER 17 TOWNSHIP NUMBER T 24 S RANGE NUMBER R 25 W

DISTANCE AND DIRECTION FROM NEAREST TOWN OR CITY STREET ADDRESS OF WELL IF LOCATED WITHIN CITY?
FROM JETMORE; APPX 8 MILES SOUTH & 10 1/4 MILES WEST

2 WATER WELL OWNER: JERRELL NUSS, INC. BOARD OF AGRICULTURE, DIVISION OF WATER RESOURCES
RR#, ST. ADDRESS, BOX #: PO BOX 518
CITY, STATE, ZIP CODE : JETMORE, KS 67854-0518 APPLICATION NUMBER:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

	NW	NE
W		
	SW	SE
X		

4 DEPTH OF COMPLETED WELL 100 ELEVATION: 0
DEPTH(S) GROUNDWATER ENCOUNTERED 1. 0 FT. 2. 0 FT. 3. 0 FT.

WELL'S STATIC WATER LEVEL 68 FT. BELOW LAND SURFACE MEASURED ON MO/DAY/YR 4/28/01
PUMP TEST DATA: WELL WATER WAS 75 FT. AFTER 2 HOURS PUMPING 83 GPM

ESTIMATED YIELD 0 GPM; WELL WATER WAS 0 FT. AFTER 0 HOURS PUMPING 0 GPM

BORE HOLE DIAMETER 11 IN. TO 100 FT., AND IN. TO 0 FT.

WELL WATER TO BE USED AS: 01 DOMESTIC

WAS A CHEMICAL/BACTERIOLOGICAL SAMPLE SUBMITTED TO DEPARTMENT? No ;
If YES, MO/DAY/YR SAMPLE WAS SUBMITTED WATER WELL DISINFECTED? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
BLANK CASING DIAMETER 6 IN. TO 100 FT., DIA IN. TO 0 FT., DIA IN. TO 0 FT.
CASING HEIGHT ABOVE LAND SURFACE 12 IN., WEIGHT 4 LBS/FT. WALL THICKNESS OR GAUGE NO. .316
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: FROM 70 FT. TO 100 FT., FROM 0 FT. TO 0 FT.
GRAVEL PACK INTERVALS: FROM 0 FT. TO 0 FT., FROM 0 FT. TO 0 FT.
FROM 20 FT. TO 100 FT., FROM 0 FT. TO 0 FT.
FROM 0 FT. TO 0 FT., FROM 0 FT. TO 0 FT.

6 GROUT MATERIAL 03 BENTONITE
GROUT INTERVALS: FROM 0 FT. TO 20 FT., FROM 0 FT. TO 0 FT., FROM 0 FT. TO 0 FT.
WHAT IS THE NEAREST SOURCE OF POSSIBLE CONTAMINATION: NONE OBSERVED
DIRECTION FROM WELL? HOW MANY FEET? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	18	01 CLAY			
18	28	07 FINE SAND 04 SANDY CLAY			
28	45	20 LIMESTONE 07 FINE SAND			
45	53	05 SAND 13 FINE GRAVEL			
53	70	01 CLAY 05 SAND			
70	83	05 SAND 14 MED GRAVEL 28 ROCK			
83	88	28 ROCK 11 GRAVEL			
88	90	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: THIS WATER WELL WAS CONSTRUCTED UNDER MY JURISDICTION AND WAS COMPLETED ON (MO/DAY/YEAR) 06/22/01 AND THIS RECORD IS TRUE TO THE BEST OF MY KNOWLEDGE AND BELIEF, KANSAS
WATER WELL CONTRACTOR'S LICENSE NO. 145 THIS WATER WELL RECORD WAS COMPLETED ON (MO/DAY/YR) 09/05/01
UNDER THE BUSINESS NAME OF HENKLE DRILLING & SUPPLY BY (SIGNATURE) *Bruce J. Reishmidt*