


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Gray	Fraction SW 1/4 SW 1/4 SW 1/4	Section number 6	Township number T 24 S R 27 E	Range number W
2. Distance and direction from nearest town or city: 12N, 1E, of Cimarron, KS Street address of well location if in city:				3. Owner of well: Max Davidson R.R. or street: City, state, zip code: Cimarron, KS 67835		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 28 in. Completion date May 17, 1977 Well depth 138 ft.		
		165' E of the SW corner of the SW 1/4, Sec. 6, T24S, R27W, Gray County, KS		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material				From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Top soil				0	6	9. Casing: Material STL Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft. Dia. 16 in. to 80 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219
Tan clay				6	20	10. Screen: Manufacturer's name Cook, Foster W/W & Millslot Type <input type="checkbox"/> Dia. 16" Slot/gauze 1/8 Length 58 Set between 80 ft. and 138 ft. ft. and <input type="checkbox"/> ft.
Caliche clay streaks				20	60	Gravel pack? <input checked="" type="checkbox"/> Size range of material 4.4mm
Tan clay				60	82	11. Static water level: <input type="checkbox"/> mo./day/yr. 80 ft. below land surface Date 12/4/76
Fine to medium sand				82	106	12. Pumping level below land surfaces: 110 ft. after 1 hrs. pumping 520 g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 520 g.p.m.
Brown clay				106	112	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
Fine to medium sand clay streaks				112	138	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> xx Inches above grade
Black shale				138	160	15. Well grouted? <input checked="" type="checkbox"/> xx With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.
(Use a second sheet if needed)						16. Nearest source of possible contamination: Unk. ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
18. Elevation:		19. Remarks:		17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 10KH HP 25 Volts 460 Length of drop pipe 130 ft. capacity 500 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co. 102 Business name License No. Address Garden City, KS Signed RL Vincent Date 26 May 77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5