

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Gray</b>	Fraction <b>NW 1/4 NW 1/4 NE 1/4</b>	Section number <b>32</b>	Township number <b>T 24 S R 27 E/W</b>	Range number <b>27</b>
2. Distance and direction from nearest town or city: <b>Jct. K-23 &amp; Pole line Rd. North of Cimarron go 3 South, Street address of well location if in city: 3 East, 1 North &amp; 1/2 West</b>	3. Owner of well: <b>Tim Dewey</b> R.R. or street: <b>R. R.</b> City, state, zip code: <b>Cimarron, KS 67835</b>				
4. Locate with "X" in section below:  Sketch map:	6. Bore hole dia. <u>28</u> in. Completion date _____ Well depth <u>153</u> ft. <u>12-30-78</u>				
5. Type and color of material	From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
<b>Top soil</b>	<b>0</b>	<b>4</b>	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
<b>Tan clay</b>	<b>4</b>	<b>30</b>	9. Casing: Material <u>Stl</u> Height: <u>Above</u> or <u>below</u> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>37</u> lbs./ft. Dia. <u>16</u> in. to <u>96</u> ft. depth   Wall Thickness: inches or Dia. <u>   </u> in. to <u>   </u> ft. depth   gage No. <u>.219</u>		
<b>Tan clay, caliche streaks</b>	<b>30</b>	<b>48</b>	10. Screen: Manufacturer's name <u>Cook, Doerr,</u> <u>Foster</u> Type <u>M/S, W/W, Louver</u> <u>16"</u> Slot/gauze <u>1/8"</u> Length <u>57</u> Set between <u>96</u> ft. and <u>153</u> ft. <u>   </u> ft. and <u>   </u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3.83 mm</u>		
<b>Fine to coarse sand, hard</b>	<b>48</b>	<b>76</b>	11. Static water level: _____ mo./day/yr. <u>84</u> ft. below land surface Date <u>11-29-78</u>		
<b>Tan sandy clay, sand streaks</b>	<b>76</b>	<b>96</b>	12. Pumping level below land surfaces: <u>130</u> ft. after <u>1/2</u> hrs. pumping <u>1248</u> g.p.m. <u>124</u> ft. after <u>1</u> hrs. pumping <u>1100</u> g.p.m. Estimated maximum yield <u>1200</u> g.p.m.		
<b>Fine to coarse sand, medium gravel, small clay streaks (loose)</b>	<b>96</b>	<b>153</b>	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____		
<b>Black shale</b>	<b>153</b>	<b>160</b>	14. Well head completion: _____ <input type="checkbox"/> Pitless adapter <u>12</u> inches above grade		
			15. Well grouted? <u>Yes</u> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
			16. Nearest source of possible contamination: <u>Unknown</u> <input checked="" type="checkbox"/> _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
			17. Pump: _____ Not installed Manufacturer's name <u>Layne &amp; Bowler</u> Model number <u>12KM</u> HP <u>56</u> Volts _____ Length of drop pipe <u>140</u> ft. capacity <u>980</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
			(Use a second sheet if needed)		
18. Elevation:	19. Remarks:				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne-Western Co., Inc. 102</b> Business name License No. Address <b>Garden City, KS 67846</b> Signed <u>[Signature]</u> Date <u>2-14-79</u> Authorized representative
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

27  
27  
32  
W  
W  
W  
NE

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5