

WATER WELL RECORD Form WWD-5 KSA 82a-1210

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY SE 1/4 SW 1/4 SE 1/4 19 T 24 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 8 MILES NORTH & 3/4 EAST OF INGALLS

2 WATER WELL OWNER: MIDWEST FEEDERS
 RR#, St. Address, Box #: 05013 "13" ROAD Board of Agriculture, Division of Water Resources
 City, State, ZIP code : INGALLS, KS 67853- Application Number: 10,999

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 248 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 138 ft. below land surface measured on mo/day/yr 07/08/97
 Pump test data: Well water was 240 ft. after 4 hours pumping 160 gpm
 Estimated Yield 160 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 248 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 248 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 39 lbs/ft. Wall thickness or gauge No. .225
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 178 ft. to 238 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 248 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 240

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	22	04 SANDY CLAY 31 CALICHE			
22	45	01 CLAY 36 GYP ROCK			
45	60	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
60	69	04 SANDY CLAY 05 SAND			
69	81	05 SAND 01 CLAY			
81	100	04 SANDY CLAY 05 SAND			
100	121	05 SAND 01 CLAY			
121	140	04 SANDY CLAY 05 SAND 20 LIMESTONE			
140	153	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/03/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/17/97 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 035 GRAY SE 1/4 SW 1/4 SE 1/4 19 T 24 S R 28 W

2 WATER WELL OWNER: MIDWEST FEEDERS

RR#, St. Address, Box #: 05013 "13" ROAD

Board of Agriculture, Division of Water Resources

City, State, ZIP code : INGALLS, KS 67853-

Application Number: 10,999

FROM	TO	LITHOLOGIC LOG
153	176	04 SANDY CLAY 20 LIMESTONE 05 SAND
176	197	05 SAND 01 CLAY
197	220	04 SANDY CLAY 05 SAND
220	238	05 SAND 01 CLAY 28 ROCK
238	245	04 SANDY CLAY 05 SAND
245	260	19 SHALE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

completed on (mo/day/year) 07/03/97 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 07/17/97

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Richman