

WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY SE 1/4 SE 1/4 SE 1/4 24 T 24 S R 29 W

12 DISTANCE AND DIRECTION FROM NEAREST TOWN OR CITY STREET ADDRESS OF WELL IF LOCATED WITHIN CITY?
 APPROX. 8 MILES NORTH OF INGALLS

12 WATER WELL OWNER: MIDWEST FEEDERS

RR#, St. Address, Box #: R.R. 1, BOX 29 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : INGALLS, KS 67853- Application Number:

13 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 252 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

 NW NE WELL'S STATIC WATER LEVEL 120 ft. below land surface measured on mo/day/yr 05/21/93
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 SW SE Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 W E Bore Hole Diameter 11 in. to 252 ft., and in. to 0 ft.
 e WELL WATER TO BE USED AS: 01 DOMESTIC
 SE Was a chemical/bacteriological sample submitted to department? No
 \ / If yes, mo/day/yr sample was submitted Water well disinfected? Yes

15 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED

Blank casing diameter 6 in. to 252 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316

16 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 202 ft. to 222 ft., From 0 ft. to 0 ft.
 From 232 ft. to 252 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 252 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

16 GROUT MATERIAL 03 BENTONITE

Grout intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? SOUTHWEST How many feet? 25

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	54	04 SANDY CLAY 31 CALICHE			
54	69	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY			
69	109	04 SANDY CLAY 07 FINE SAND			
109	117	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
117	122	04 SANDY CLAY 20 LIMESTONE			
122	135	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
135	147	04 SANDY CLAY			
147	167	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
167	185	04 SANDY CLAY			

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/29/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	I Fraction			I Section Number	I Township Number	I Range Number
COUNTY: 035 GRAY	I SE	1/4 SE	1/4 SE	1/4	I 24	I T 24 S I R 29 W

12 WATER WELL OWNER: MIDWEST FEEDERS

RR#, St. Address, Box #: R.R. 1, BOX 29

City, State, ZIP code : INGALLS, KS 67853-

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
185	193	07 FINE SAND 08 MEDIUM SAND
193	201	04 SANDY CLAY
201	212	07 FINE SAND 09 COARSE SAND 29 ROCK & SAND
212	236	04 SANDY CLAY
236	250	07 FINE SAND 09 COARSE SAND 29 ROCK & SAND
250	253	31 CALICHE
253	260	19 SHALE

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/29/93 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reckmatt*