

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	SW 1/4 SW 1/4 SE 1/4	24	T 24 S	R 29 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 7 3/4 MILES NORTH & 1/2 MILE WEST OF INGALLS

2 WATER WELL OWNER:	MIDWEST FEEDERS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	05013 13 RD	

City, State, ZIP code :	INGALLS, KS 67853-9023	Application Number: 10,639 & 32,786
-------------------------	------------------------	-------------------------------------

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 277 ELEVATION: 0
	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
/ \	WELL'S STATIC WATER LEVEL 120 ft. below land surface measured on mo/day/yr
1	Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
M	Estimated Yield 250 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
i	W Bore Hole Diameter 17.5 in. to 277 ft., and in. to 0 ft.
1	E
e	WELL WATER TO BE USED AS: <u>03 FEEDLOT</u>
\ /	Was a chemical/bacteriological sample submitted to department? No ;
---	If yes, mo/day/yr sample was submitted Water well disinfected? Yes
X	

5 TYPE OF BLANK CASING USED: 02 PVC	CASING JOINTS: GLUED
Blank casing diameter 8 5/8 in. to 277 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. .410	
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC	
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT	

SCREEN PERFORATED INTERVALS:	From 127 ft. to 147 ft., From 207 ft. to 227 ft.
	From 167 ft. to 187 ft., From 247 ft. to 267 ft.
GRAVEL PACK INTERVALS:	From 25 ft. to 277 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	How many feet? 290
Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: 14 ABAND. WELL	
Direction from well? SOUTH	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	28	01 CLAY			
28	50	36 GYP ROCK 01 CLAY			
50	59	05 SAND 13 FINE GRAVEL			
59	75	05 SAND 11 GRAVEL			
75	79	01 CLAY			
79	88	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
88	103	01 CLAY 04 SANDY CLAY 05 SAND			
103	112	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY			
112	147	05 SAND 11 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>constructed</u> under my jurisdiction and was completed on (mo/day/year) 07/28/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 08/14/98
under the business name of HENKLE DRILLING & SUPPLY	by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	SW 1/4 SW 1/4 SE 1/4	24	T 24 S	R 29 W

2 WATER WELL OWNER:	MIDWEST FEEDERS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	05013 13 RD	

City, State, ZIP code :	INGALLS, KS 67853-9023	Application Number: 10,639 & 32,786
-------------------------	------------------------	-------------------------------------

FROM	TO	LITHOLOGIC LOG
147	160	01 CLAY 20 LIMESTONE
160	167	05 SAND 28 ROCK
167	178	05 SAND 13 FINE GRAVEL 28 ROCK
178	190	04 SANDY CLAY 07 FINE SAND
190	200	01 CLAY
200	226	05 SAND 28 ROCK 01 CLAY
226	251	01 CLAY 04 SANDY CLAY 20 LIMESTONE
251	258	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY
258	267	07 FINE SAND 08 MEDIUM SAND 28 ROCK
267	270	01 CLAY
270	275	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/28/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/14/98 under the business name of HENKLE DRILLING & SUPPLY	by (signature) <i>Bruce J. Reichmuth</i>
--	--