


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Harvey	SE 1/4 SE 1/4 SE 1/4	23	T 24 S	R 3 E/W

Distance and direction from nearest town or city street address of well if located within city?

Approximately 2 1/2 miles east of Patterson

2 WATER WELL OWNER:	City of Wichita
RR#, St. Address, Box # :	455 N. Main
City, State, ZIP Code :	Wichita, KS 67202
	Board of Agriculture, Division of Water Resources
	Application Number: 1006

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 185 ft. ELEVATION: Unknown
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL 31 ft. below land surface measured on mo/day/yr 5-21-96
	Pump test data: Well water was Not ch'd ft. after hours pumping gpm
	Est. Yield unknown gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter 42 in. to 185 ft., and in. to ft.
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes ☒ No	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below) Welded ☒
2 PVC	4 ABS	7 Fiberglass	8 Air conditioning 11 Injection well
Blank casing diameter steel 18 in. to 59 ft., Dia. steel 18 in. to 64 ft., Dia. 18" to 89" in. to 18" to 184" ft.	Stainless steel	Stainless steel	Threaded. stainless steel
Casing height above land surface steel 12 in., weight 70.59 lbs./ft. Wall thickness or gauge No. 375	stainless steel 47.17 lbs./ft.	250 wall thickness	
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
SCREEN-PERFORATED INTERVALS: From 64 ft. to 79 ft., From ft. to ft.			
From 89 ft. to 179 ft., From ft. to ft.			
GRAVEL PACK INTERVALS: From 20 ft. to 185 ft., From ft. to ft.			
From ft. to ft., From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft.				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
13 Insecticide storage None known				
Direction from well? How many feet?				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PERFORATION INTERVALS
0	2	Topsoil	135	146	Sand and gravel, fine, medium
2	9	Clay, brown	146	156	Clay, brown
9	17	Clay, gray	156	165	Sand, very fine, fine
17	48	Sand, fine, medium, coarse	165	180	Sand, fine, medium with some clay
48	56	Sand, fine, medium	180	185	Clay, brown
56	60	Clay, green			
60	70	Sand, fine, medium			
70	72	Clay, black			
72	80	Sand and gravel with some clay, gray			
80	90	Clay, black and gray			
90	96	Clay, brown			
96	100	Clay, brown with gravel, medium			
100	130	Sand and gravel, fine			
130	135	Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-21-96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 5-23-96 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>
--