

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Harvey		NC E $\frac{1}{2}$ XX W $\frac{1}{2}$ XX SW $\frac{1}{4}$		1		T 24 S		R 3 E/W	
Distance and direction from nearest town or city street address of well if located within city? Approximately 5 miles west and 3/4 mile south of Halstead									
2 WATER WELL OWNER:		Eugene Wendling							
RR#, St. Address, Box # :		1010 Chestnut							
City, State, ZIP Code :		Halstead, KS 67056							
		Board of Agriculture, Division of Water Resources Application Number: 32,858							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 260 ft. ELEVATION: unknown							
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL . 48.4 . ft. below land surface measured on mo/day/yr 4-29-94 Pump test data: Well water was not ch'd. ft. after hours pumping gpm Est. Yield unknown gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter . 36 . in. to 260 . ft., and . in. to . ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes.....No.....X..... If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes X No							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued . X . Clamped . 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded . 2 PVC 4 ABS 7 Fiberglass Threaded . Blank casing diameter . 16 . in. to 89 . ft., Dia . 16 . in. to 199 . ft., Dia . in. to . ft. Casing height above land surface . 12 . in., weight . 19.75 . lbs./ft. Wall thickness or gauge No. . 616							
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)							
SCREEN-PERFORATED INTERVALS:		From . 89 . ft. to 127 . ft., From . ft. to . ft. From . 199 . ft. to 259 . ft., From . ft. to . ft. GRAVEL PACK INTERVALS: From . 50 . ft. to 160 . ft., From . ft. to . ft. From . 160 . ft. to 260 . ft., From . ft. to . ft.							
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other Road sand Grout Intervals: From . 0 . ft. to 2 . ft., From . 2 . ft. to 22 . ft., From . 22 . ft. to 50 . ft.							
What is the nearest source of possible contamination:		1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage None known							
Direction from well?		How many feet?							
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0 3 Topsoil		116 117 Clay, gray							
3 7 Sand, fine		117 130 Sand and gravel							
7 12 Sand and gravel		130 148 Clay, brown							
12 14 Clay, brown		148 151 Sand and gravel							
14 20 Clay, with sand streaks		151 165 Clay, black							
20 28 Sand and gravel, medium		165 195 Clay, black to gray							
29 30 Clay, brown		195 260 Sand, fine to medium, very clean, loose							
30 51 Sand and gravel		260 Shale							
51 60 Clay, green									
60 68 Sand, fine, clay, soft, green									
68 74 Clay, green to gray									
74 90 Sand, fine with clay									
90 103 Sand and gravel, medium									
103 104 Clay, green									
104 116 Sand and gravel									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4-29-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 5-10-94 under the business name of Clarke Well & Equipment, Inc. by (signature)									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									