

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Harvey	Fraction center of 1/4 1/4 SW 1/4	Section number 16	Township number T 24 S R 3 E (W)	Range number		
2. Distance and direction from nearest town or city: Street address of well location if in city: 1W 1 1/4 N Patterson			3. Owner of well: Ivan Hunt R.R. or street: City, state, zip code: Sedgwick, Kansas					
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: open field		6. Bore hole dia. 30 in. Completion date: 5/22/79 Well depth 72 ft.				
5. Type and color of material		From To		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary				
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other				
				9. Casing: Material C-Asb Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft.				
				Dia. 16 in. to 72 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 3/4"				
				10. Screen: Manufacturer's name Johnson Type Cement-Asb Dia. 16" Slot/gauze 1/4" Length 26' Set between 46 ft. and 72 ft. ft. and ☐ ft. Gravel pack? ☒ Size range of material 3/8				
Topsoil		0		1		11. Static water level: ☐ mo./day/yr. 12 ft. below land surface Date ☐		
Fine Sand		1		15		12. Pumping level below land surfaces: 20 ft. after 1 hrs. pumping 600 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 900 g.p.m.		
Fine Sand/Gray Clay		15		20		13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
Clay		20		35		14. Well head completion: ☐ Pitless adapter 12 Inches above grade		
Med. Sand		35		50		15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
Gravel		50		72		16. Nearest source of possible contamination: none ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
						17. Pump: Not installed Manufacturer's name Peerless Model number G108898 HP 60 Volts ☐ Length of drop pipe 60 ft. capacity 800 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name Maize License No. ☐ Address ☐ Signed H. Weninger Date 6/20/79 Authorized representative				