


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Harvey	Fraction SW 1/4 NE 1/4 NW 1/4	Section number 17	Township number T 24 S	Range number R 3W E (NW)
2. Distance and direction from nearest town or city: 6 miles N & 3/4 mile W, and 1/4 south of Mt. Hope, Ks			3. Owner of well: Eugene Wolf R.R. or street: R.R. #2 City, state, zip code: Burrton, Kansas			
4. Locate with "X" in section below: 			Sketch map: 6. Bore hole dia. 30 in. Completion date 3-22-78 Well depth 89 ft. 7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☒ Reverse rotary 8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Transite Height: Above or below surface 12 in. See # 19 Below RMP ☐ PVC ☐ Weight 37 lbs./ft. Dia. 16 in. to 89 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 3/4"			
5. Type and color of material			From	To		
Top Soil			0	1	10. Screen: Manufacturer's name Johnson Type irrigator Dia. 16" Slot/gauze .100 Length 23' Set between 20' ft. and 33' ft. 78 ft. and 88' ft.	
Brown Sandy Silt			1	3	Gravel pack? yes Size range of material 1/2-1/8	
Fine to Coarse Sand			3	10	11. Static water level: 6 ft. below land surface Date 3-22-78	
Medium to Coarse Sand and Gravel			10	32	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.	
Clay			32	40	13. Water sample submitted: ____ mo./day/yr. ☐ Yes ☐ No Date ____	
Fine Sand			40	48	14. Well head completion: 12 capped ☐ Pitless adapter ____ inches above grade	
Clay			48	71	15. Well grouted? Yes 1-2 Fine Sand Mix With: ____ Neat cement ____ Bentonite ____ Concrete Depth: From 0 ft. to 10 ft.	
Medium to Coarse Sand and Fine to Medium Gravel			71	88	16. Nearest source of possible contamination: None ft. ____ Direction ____ Type ____ Well disinfected upon completion? ☒ Yes ☐ No	
Clay			88	89	17. Pump: ☒ Not installed Manufacturer's name ____ Model number ____ HP ____ Volts ____ Length of drop pipe ____ ft. capacity ____ g.p.m. Type: ____ Submersible ____ Turbine ____ Jet ____ Reciprocating ____ Centrifugal ____ Other ____	
(Use a second sheet if needed)						
18. Elevation:	19. Remarks: Flat Ground From # 9 above- Banded but Joint No apparent source for contamination.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 4-15-78 Authorized representative			